IMPORTANT!
Before proceeding with plumbing and electrical installation, comply with all applicable utility codes and regulations.

DENTALEZ

Chair Side

21 1/16"

18"

AIR
Ø 5/8" through

(if applicable):
80-100 PSI
1/2" (1.3 cm) pipe with 1/2" M.N.P.T. by contractor. Protrude 1¼" (3.2 cm) max. from wall or floor. Purge line of all debris. Terminate w/ shut-off valve supplied by dental dealer, installed by contractor.

Chair Center Line See Note on Utilities Center Line

3½"

Utilities Center Line Locate utilities center line on chair center line 9.5" from edge of chair base.

2" **2"**

***DRAIN**
Ø 7/8" through

(if applicable):
3/4" (1.9 cm) rigid copper tubing or PVC fittings (PVC fittings not supplied). Stub up 1¼" (3.2 cm) max. from floor. NOTE: Trap and vent as per local code by contractor.

11"

VACUUM
Ø 5/8" through

(if applicable):
1/2" (1.3 cm) rigid copper tubing or PVC fittings (PVC fittings not supplied). Protrude 1¼" (3.2 cm) max. from wall or floor. NOTE: Plumbing up to utility service center box to be specified by central vacuum supplier.

***WATER**
Ø 5/8" through

(if applicable):
40-45 PSI,
1/2" (1.3 cm) pipe with 1/2" M.N.P.T by contractor. Protrude 1¼" (3.2 cm) max. from wall or floor. Purge line of all debris. Terminate with shut-off valve supplied by dental dealer, installed by contractor.

3"

Electrical Outlet Location

4X FOR #10-32 ANCHORS

ELECTRICAL
Provide 120V, 20 amp power supply with duplex receptacle by contractor.

15"

IMPORTANT NOTE
It is not necessary to install utilities to support optional equipment. But, if use of optional equipment is a consideration for the future, it is highly recommended to install the required utilities at this time.

***Optional Equipment**

Forest EQUIPMENT

6400 CHAIR USC
FULL SIZE TEMPLATE

PN: 2677-101A
FEBRUARY, 2022